





3HRH400		
TDH	L/Min	L/Day
10	31	11,160
15	30	10,800
20	29	10,440
25	28	10,080
30	27	9,720
40	23	8,280
50	20	7,200
60	15	5,400
70	12	4,320
\$4,600+ G ST		

Bore part #: 3HRH400-B40 **Dam Floating** part #: 3HRH400-D40 inc 40m cabling & delivery to Geraldton

L/Day TDH L/Min 18,360 10 51 20 50 18,000 30 47 16,920 40 46 16,560 50 44 15,840 42 15,120 60 70 39 14,040 36 80 12,960 33 11,880 90 100 28 10,080 110 25 9,000 120 20 7,200 5,400 130 15

4HRH1100

FEATURES

- Brushless DC motor
- Integrated Soft start & MPPT
- Adjustable Speed & Timer Control
- All Stainless Steel
- **High Efficiency**
- TIE E RBO

Pump, motor, controller





Heavy Duty Cyclone Rated Pole **Mount Frame**

+ Easy DIY installation manual

+ Spare helical rotor

Mono Crystalline Solar Panels



Flow rate up to 18,360 L/day

High reliability & life expectancy

Power Cable Low Water Probe & Safety Cabling



Bore kit or

Dam kit



2 years manufacturer's warranty against defects in material & workmanship. Anodes are recommended for all bore installations, \$90 + GST each.

\$6,100+gst Bore part #: 4HRH1100-B40 Dam Floating part #: 4HRH1100-D40 inc 40m cabling & delivery to Geraldton





EACH WATERBOY SOLAR PUMP SYSTEM INCLUDES:

.

.

BENEFITS

Lift up to 130m

Simple installation

Maintenance-free

